Carpentry Work

Scope:- These specifications are intended to cover the furnishing, delivery and erection of all carpentry work, required to complete the building, whether shown, specified or not, including doors, hatch covers, flag pole, etc.

General:- All exterior doors to be weather, rain and of light tight, top, bottom and sides.

Rough Work:- Furnish all rough carpentry, temporary or preparatory work for the complete building, including forms, all wood framing for centers, scaffolding, etc., and all rough hardware.

Wooden Doors:- All exterior woodwork to be clear cypress or grade "A" White Pine. Doors and frames to be well put together in accordance with first class mill practice, as per detail drawings to be furnished. Large double doors 2-1/4" thick, all other doors 1-3/4" thick; bottom stiles 12" wide, side and top 8" wide V-grooved panels 1-1/8" thick. Interior wooden doors to be clear White Pine.

Metal Covered Doors:- South exterior doors to be Kalamein or metal covered, glazed, as shown.

Glazing:- Windows and doors to be glazed as called for on drawings.